

CITY OF CHANHASSEN
STANDARD SPECIFICATIONS REVISIONS
Rev. 2024

GENERAL CONDITIONS

- Section 1.07 Part 1--Added Contractor Verification of Compliance and Responsible Contractor Verification of Compliance to the list of Contract Documents.
- Section 7.02 2nd Paragraph--Added- “In addition to the aforementioned construction hours, on October 31st operations must cease by 3:00 p.m. (no construction activities are allowed on Sundays).”
- Section 9.19 Part 1B1--added for clarification “Only the curb box swing tie applicable for the lot it is servicing shall be shown on the tie card.”

STREETS

- Section 1.03 2nd Paragraph-- Language added—Review full paragraph.
- Section 3.01 Section revised and addition of Part B--Review entire section.
- Section 4.10 Part A—Additional numbered point added—Review all.
- Section 4.11 Part A-1c—Language changed "The upper section shall weigh 3 lbs/ft" to “The upper section shall weigh 2.5 lbs/ft”
- Section 4.14 Part A-2—Language added “Sod shall be from vendors on the “Approved/Qualified Products List”
Part A-5—Language changed “topsoil which does not meet MnDOT Specification No. 3877...” to “topsoil which does not meet City specifications for topsoil material...”
Part A-10—Language added “Watering may occur on Sunday’s if written approval is provided by the City Engineer or their designee.”
Part D-- Section revised--Review entire section.

WATER MAIN

- Section 2.04 1st paragraph and Part B--Wording changed for clarification “corresponding to a working pressure of 150 PSI for PVC type 1120 pipe” changed to “corresponding to a working pressure of 200 PSI for PVC type 1120 pipe.”
- Section 2.06 Section revised--Review entire section.
- Section 2.11 Review manufacturer parts.
- Section 2.12 Review manufacturer parts.
- Section 2.13 Last paragraph-- Language added—Review full paragraph.

Section 6.08 Part A: Language added for clarification "...SDR 11.0, with coextruded blue dual stripes."

Section 14.03 Section revised: Review entire section.

SANITARY AND STORM

Section 2.11 Wording changed for clarification throughout this section from "Standard plate to Detail plate"

Section 2.12 1st paragraph: Language added—Review full paragraph.

Section 2.19 Wording changed for clarification throughout this section from "Standard plate to Detail plate"

Section 7.02 Wording changed for clarification throughout this section from "Standard plate to Detail plate"
Part A, 2nd Paragraph--Added: Televising inspections in accordance with Section 19.00 shall be conducted after the deflection is checked."
Part A, last Paragraph—Wording changed for clarification "performed if applicable" changed to "performed at the direction of the City Engineer."

Section 8.03 Wording changed for clarification throughout this section from "Standard plate to Detail plate"

Section 10.01 Wording changed for clarification throughout this section from "Standard plate to Detail plate"

Section 11.05 1st paragraph: Language added—Review full paragraph.
3rd paragraph—Wording changed for clarification "performed if applicable" changed to "performed at the direction of the City Engineer."

Section 12.03 Wording changed for clarification throughout this section from "Standard plate to Detail plate"

Section 12.05 Section revised: Review entire section.

Section 12.09 2nd paragraph: Removed "Detail Plate #2104A"

Section 12.10 Language added—"If debris enters the sanitary system, the system shall be adequately cleaned, jetted, and televised within 48-hours to the satisfaction of the Engineer at no cost to the Owner."

Section 17.08 Wording changed for clarification throughout this section from "Standard plate to Detail plate"

Section 19 Language added—"...leak testing and deflection testing have been completed and accepted...."

Section 19.03 Language added--"... in certified PACP format, and a PACP compliant database on a digital hard drive..."

Section 20.03 Part A--Language added—Review full paragraph.

SANITARY SEWER REHABILITATION

No Revisions for 2024

TRACE WIRE

Section 2.0 Installation: 7th bullet point-Italicized portion –added language to the end of the statement.
Testing: --Review all.
Products: --Review all.

LANDSCAPE

Section 2.02 Part A. Soil Amendments - 1. MnDOT -3877 –added “(as modified by Chanhassen Street Construction Specifications Section 4.14D)”

STANDARD DETAIL PLATE REVISIONS

- 1004: Added Drawing Comment- “Secure Tracer Wire to the Plastic Wrap with Tape.”
Update to Drawing- “Strap and Stainless-Steel Band Replaced with Field Weld...”
- 1005: Added Drawing Comment- “Do Not install Riser Rod.”
- 1006: Added Drawing Comment- “Do Not install Riser Rod.”
- 1010: Added Drawing Comment/Note 2.- “Pressure Gauges Shall be Stainless-Steel...”
- 1012: New Detail Plate- D.I.P. Conductivity
- 1013: New Detail Plate- Sacrificial Anode Bag Installation
- 2001: Updated Drawing Comments/Notes- Review All
- 2002: Added Drawing Comments/Notes- Review All
- 2101: Updated Drawing Comments/Notes 4 & 5- Step Installation
- 2104: Added Drawing Comments/Note 14- Soil Compaction
- 2110: Added Drawing Comments/Note 1- Adjusting Rings
- 3100: Updated Drawing Comments- Manhole Steps & Precast Base
- 3101: Added Drawing Comments/Note 4- Drantile Installation
- 3102: Updated Drawing Comments/Note 4- Manhole Steps, Precast Base & Tracer Wire
Access Box -Drantile Installation
- 3103: Updated Drawing Comments- Reference to Detail Plate 2110
- 3106: Updated Drawing Comments- “Long Epoxy Coated Rebar”
Added Comment 1- Drantile Installation
- 3109B: Updated Drawing Comments- Manhole Steps
Added Notes 1-3
- 3110: Updated Drawing Comments/Notes- Manhole Steps
- 5200: Updated Drawing Comments/Note 6- Aggregate Base
Added Drawing Comments/Note 8- Small Utilities
- 5201: Updated Drawing Comments/Note 6- Aggregate Base
Added Drawing Comments/Note 8- Small Utilities
- 5202: Updated Drawing Comments/Note 6- Aggregate Base
Added Drawing Comments/Note 7- Small Utilities

5203: Added Drawing Comments/Notes- Review All

5205B: Updated Drawing Comments- Minimum Radius

5208: Detail Plate 5208 Split to Create New Plates 5208A & 5208B- Review All

5209: Detail Plate 5209 Split to Create New Plates 5209A & 5209B- Review All

5217: Updated Drawing Comments/Note 1- Street Maintenance Foreman-contact info.

5221: Updated Drawing Comments- Sketch Section

5232: Updated Drawing Comments/Notes- Perforated Pipe

5233: Updated Drawing Comments- Manhole Connection Detail

5235: Updated Drawing Comments/Notes- Review All

5236: Updated Drawing Comments/Notes- Incorporated Updates from Plate 5235

5240: Added Drawing Comments- 4' Min Base to Back of Curb

5244: Added Drawing Comments- Sign Insert

5302A: Added Drawing Comments/Note 3- Sediment Trap

5302B: Updated Drawing Comments/Notes- Review All

5302C: Updated Drawing Comments/Notes- Review All

5302D: Updated All Notes- Review All

5302E: Restructured Plates 5302A-D leaving Blank Plate for E-reserved for future use

5503: Added Drawing Comments/ Note 6- Review All

5506: Added Drawing Comments/Notes- Review All

5508: Added Drawing Comments/Notes- Review All