

EROSION AND SEDIMENT CONTROL STANDARD NOTES

1. EROSION CONTROL MUST BE INSTALLED AND INSPECTED PRIOR TO THE START OF LAND DISTURBING ACTIVITIES INCLUDING TREE REMOVAL AND GRADING.
 - 1.1. CONTACT ENGINEERING DEPARTMENT TO SCHEDULE AN INSPECTION 952-227-1160 OR ENGDEPT@CHANHASSENMN.GOV
2. THE CONTRACTOR SHALL ABIDE BY ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES DICTATED BY THE CITY OF CHANHASSEN AND WATERSHED DISTRICT.
3. OPERATIONS MUST BE MANAGED TO ELIMINATE TRACK OUT OF MATERIAL ONTO RIGHT OF WAY.
4. STRAW MULCH SHALL NOT BE USED FOR TEMPORARY OR FINAL STABILIZATION UNLESS APPROVED BY THE CITY ENGINEER.
5. NATURAL TOPOGRAPHY AND SOIL CONDITIONS MUST BE PROTECTED, INCLUDING RETENTION ONSITE OF NATIVE TOPSOIL TO THE GREATEST EXTENT POSSIBLE.
6. ADDITIONAL MEASURES, SUCH AS HYDRAULIC MULCHING AND OTHER PRACTICES AS SPECIFIED BY THE DISTRICT AND CITY STAFF MUST BE USED ON SLOPES OF 3:1 (H:V) OR STEEPER TO PROVIDE ADEQUATE STABILIZATION.
7. FINAL SITE STABILIZATION MEASURES MUST SPECIFY THAT AT LEAST SIX INCHES OF TOPSOIL OR ORGANIC MATTER BE SPREAD AND INCORPORATED INTO THE UNDERLYING SOIL DURING FINAL SITE TREATMENT WHEREVER TOPSOIL HAS BEEN REMOVED.
8. CONSTRUCTION SITE WASTE SUCH AS DISCARDED BUILDING MATERIALS, CONCRETE TRUCK WASHOUT, CHEMICALS, LITTER AND SANITARY WASTE MUST BE PROPERLY MANAGED.
9. ALL TEMPORARY EROSION AND SEDIMENT CONTROL BMPS MUST BE MAINTAINED UNTIL COMPLETION OF CONSTRUCTION AND VEGETATION IS ESTABLISHED SUFFICIENTLY TO ENSURE STABILITY OF THE SITE, AS DETERMINED BY THE WATERSHED DISTRICT AND CITY STAFF.
10. SOIL SURFACES COMPACTED DURING CONSTRUCTION AND REMAINING PVIOUS UPON COMPLETION OF CONSTRUCTION MUST BE DECOMPACTED TO ACHIEVE A SOIL COMPACTION TESTING PRESSURE OF LESS THAN 1,400 KILOPASCALS OR 200 POUNDS PER SQUARE INCH IN THE UPPER 12 INCHES OF THE SOIL PROFILE WHILE TAKING CARE TO PROTECT UTILITIES, TREE ROOTS, AND OTHER EXISTING VEGETATION.
11. ALL DISTURBED AREAS MUST BE STABILIZED WITHIN 7 CALENDAR DAYS AFTER LAND-DISTURBING WORK HAS TEMPORARILY OR PERMANENTLY CEASED ON A PROPERTY THAT DRAINS TO AN IMPAIRED WATER, WITHIN 14 DAYS ELSEWHERE.
12. THE PERMITTEE MUST, AT A MINIMUM, INSPECT, MAINTAIN AND REPAIR ALL DISTURBED SURFACES AND ALL EROSION AND SEDIMENT CONTROL FACILITIES AND SOIL STABILIZATION MEASURES EVERY DAY WORK IS PERFORMED ON THE SITE AND AT LEAST WEEKLY UNTIL LAND-DISTURBING ACTIVITY HAS CEASED. THEREAFTER, THE PERMITTEE MUST PERFORM THESE RESPONSIBILITIES AT LEAST WEEKLY UNTIL VEGETATIVE COVER IS ESTABLISHED. THE PERMITTEE WILL MAINTAIN A LOG OF ACTIVITIES UNDER THIS SECTION FOR INSPECTION BY THE WATERSHED DISTRICT AND CITY ON REQUEST.



EROSION AND SEDIMENT CONTROL STANDARD NOTES

REVISED: 2-24

ENGINEERING DEPARTMENT

PLATE NO.:

5302D