



NOTES:

1. CLEANOUTS REQUIRED AT 200' MAXIMUM INTERVALS & ALL ENDING POINTS.
2. SWING TIES TO BE SHOWN ON AS-BUILTS FOR ALL CLEANOUTS AND ENDING POINTS TO ALL DRAINTILES.
3. OPENINGS IN STRUCTURE FOR DRAINTILE TO BE PREFABRICATED ON CORE DRILLED.
4. ALL DRAINTILES TO HAVE TRACER WIRES.



EACH STRUCTURE SHALL BE CHECKED FOR BUOYANCY AND CERTIFIED BY THE ENGINEER OF RECORD THAT FLOTATION WILL NOT OCCUR.



**CITY OF
CHANHASSEN**

ALTERNATE 4"
SUB-SURFACE
DRAINTILE

REVISED: 2-22

FILE NAME: G:\ENG\SPECS\5233

ENGINEERING DEPARTMENT

PLATE NO.:

5233